

MARYLAND HISTORICAL TRUST ADDENDUM SHEET
U.S. 301 SOUTH CORRIDOR TRANSPORTATION STUDY

Property Name: Gwynn Park
Survey No.: PG:85A-13

Property Address 7911 and 9110 Dyson Road, Brandywine Vicinity, Prince George's County
Owner Name/Address Route 301-CPI Assoc. LTD. Partnership/Capitol Properties Inc. Box 740 Warrenton, VA
20186
Year Built 1857

Description:

Gwynn Park was previously surveyed by Prince George's County Historic Preservation Commission in 1998, P.A.C. Spero and Company in 1996, amended in 1998 and the Maryland National Capital Parks and Planning Commission in 1974. It was noted in the addendum prepared by Spero in 1998 that the tenant house associated with Gwynn Park had been destroyed by fire. The two outbuildings associated with the tenant house were still extant. EHT Traceries, Inc. conducted a follow-up survey in February 2000 to reevaluate the Gwynn Park resource boundary for National Register eligibility and to access any changes in physical condition of the resources since 1998. The "Board of Education" school building, located in the center of the proposed boundary, is considered a non-contributing element to the National Register boundaries of Gwynn Park. Consequently, Traceries recommends revising the proposed boundary so that the new boundary includes the school building as a non-contributing resource. The boundary as revised, follows the tax parcel of the historic resources and includes the school building parcel in the center of the assemblage.

National Register Evaluation:

Gwynn Park (PG:85A-13) was determined eligible for the National Register of Historic Places by the Maryland Historical Trust in a letter dated July 21, 1997. The boundaries for the eligible property include the main house and its various outbuildings on the southeast side of Dyson Road, and the ruins of the tenant house and its two outbuildings on the northwest side of Dyson Road. The 20th century school site and parking lot, located in the center of the Gwynn Park site, is a non-contributing element. Although the tenant house is no longer extant, there is an excellent possibility that archaeological resources are located on the site. The National Register boundaries of Gwynn Park is bounded on the southeast by U.S. 301 and on all other sides by adjacent tax parcels. Although the property's total acreage has been reduced from its original holdings of 510 acres, the remaining acreage associated with the historic property that has not been redeveloped is included within the National Register boundaries.

MHT CONCURRENCE:

Eligibility ☒ recommended ☐ not recommended

Criteria ☐ A ☐ B ☐ C ☐ D Considerations ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☐ None

Comments:

Reviewer, Office of Preservation Services

7/21/97
Date

Reviewer, NR program

B. Kuntz
Date


8/14/00
Date

8/14/00
Date

gms

Property Address 7911 and 9110 Dyson Road, Brandywine Vicinity, Prince George's County
Owner Name/Address Route 301-CPI Assoc. LTD. Partnership/Capitol Properties Inc. Box 740 Warrenton, VA
20186
Year Built 1857

Resource Sketch Map:





TEA - 5

6/27/10 1/2 R

1/2 R 1/2 R 1/2 R 1/2 R 1/2 R

1/2 R 1/2 R 1/2 R

1/2 R

1/2 R 1/2 R

1/2 R 1/2 R 1/2 R 1/2 R 1/2 R

1/2 R



70 20 10
10000 PARK
10000 GERRARD - 100 110
10000 TYPICAL
9-95
10000 10
10000 10000 10 10
10000 10000 10 10

MARYLAND HISTORICAL TRUST ADDENDUM SHEET
MD 5 Brandywine Interchange

Property Name: Gwynn Park
Survey No.: PG: 85A-13

Property Address 7911 and 9110 Dyson Road, Brandywine Vicinity, Prince George's County
Owner Name/Address Route 301-CPI Assoc. Ltd. Partnership/Capitol Properties Inc., Box 740, Warrenton, VA 20186
Year Built 1857

Description:

Gwynn Park was previously surveyed by the Maryland-National Capital Parks and Planning Commission (M-NCPPC) in 1974, by the Prince George's County Historic Preservation Commission in 1998, and by P.A.C Spero & Company in 1996. Since that time, the associated tenant house has been destroyed by fire. The two outbuildings associated with the tenant house are still extant.

The property was determined eligible for the National Register of Historic Places by the Maryland Historical Trust in a letter dated July 21, 1997.

MHT CONCURRENCE:

Eligibility ☒ recommended ☐ not recommended

Criteria ☐ A ☐ B ☐ C ☐ D Considerations ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☐ None


Comments: Continue to consider with MHT 7/21/97
determination

Oldender 12/8/98
Reviewer, Office of Preservation Services Date

B. Kuntz 12/18/98
Reviewer, NR program Date


July

MD 5 Brandywine Interchange
Town/County T.B. Vicinity/Prince George's
Quad Brandywine, MD
Survey No. PG:85A-13 (PACS 1.5)
Property Name Gwynn Park



Property Name: Gwynn Park
Survey No.: PG: 85A-13 (PACS B92)

Resource Sketch Map and National Register Boundary Map:



U.S. 301 South Corridor


Transportation Study


Survey # B92, PG:85A-13

Property Name GWYNN PARK

Town/County BRANDYWINE/Prince George's Co.

Quadrangle Brandywine







PG:85A-13



PG:85A-13





PG:85A-13

MARYLAND HISTORICAL TRUST CONTINUATION SHEET
U.S. 301 SOUTH CORRIDOR TRANSPORTATION STUDY

Property Name: Gwynn Park
Survey No.: PG: 85A-13 (PACS B92)

Property Address 7911 and 9110 Dyson Road, Brandywine, Prince George's County
Owner Name/Address Route 301-CPI Associates Limited Partnership/Capitol Properties Inc., 8341-A Greensboro
Drive, McLean, VA 22102 Year Built 1857

Description:

Gwynn Park was previously surveyed by the Maryland-National Capital Park and Planning Commission (M-NCPPC) in 1974 and by the Prince George's County Historic Preservation Commission in 1988. Since the time of the previous survey, the property has been sold, resulting in a reduction in the acreage of the property from 118.57 hectares (293 acres) to 77.27 hectares (190.95 acres). The house is currently unoccupied.

In addition, a 2-story, 3-bay I-house is located across Dyson Road from the main house, and was not noted in the previous surveys. The structure, which was likely a tenant house for Gwynn Park, is currently located on the same tax parcel as the main house and its outbuildings. The house has a 1-story, full-width, shed roof porch on the front, or south elevation and an end-wall brick chimney. It has a 2-story, shed roof addition on the north or rear elevation with an exterior brick chimney. In addition, there are two outbuildings associated with the structure; a 1-story wood-frame shed and a 1-story concrete block shed. The house is currently vacant and in deteriorated condition.

National Register Evaluation:

Gwynn Park is an excellent example of a Georgian plantation house of the mid-nineteenth century, and is eligible for the National Register of Historic Places under Criterion C. The property is not eligible under Criterion A, as research conducted indicates no association with any historic events or trends significant in the development of national, state or local history. Historic research indicates that the property has no association with persons who have made specific contributions to history, and therefore, it does not meet Criterion B. The property meets Criterion C as an excellent example of a Georgian dwelling with a decorative molded brick cornice. The integrity of the structure is high and the property retains considerable acreage, preserving its rural setting. Based upon the date of construction and the property type, there is a likelihood that an archaeological component could exist on the property. However, as no archaeological investigation has been conducted, the eligibility of the property under Criterion D cannot be assessed at this time.

Verbal Boundary Description and Justification:

The National Register boundaries of Gwynn Park follow the current property lines of Parcel 166 on Prince George's County Tax Map 145. This parcel is bounded on the southeast by U.S. 301 and on all other sides by adjacent tax parcels. The property included 206.39 hectare (510 acres) in 1873 and was not reduced in size until 1955, when the property included 150.05 hectare (370.785 acres). By 1988, the property included 118.57 hectare (293 acres), and the parcel is currently 77.27 hectare (190.95 acres). The boundary includes all the acreage remaining with the property, the main house, the tenant house and its outbuildings, a meat house, a small barn, a corn crib, a tobacco barn, and a modern garage. All structures on the property contribute to its significance, with the exception of the modern garage, which is a non-contributing element. Acreage which was historically associated with the property but is now in other ownership has not been included in the boundary, as the surrounding area has been developed, including the construction of two school buildings.

MHT CONCURRENCE:

Eligibility ☒ recommended ☐ not recommended

Criteria ☐ A ☐ B ☒ C ☐ D Considerations ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G ☐ None

Comments:


Suzanne Pickens 07/21/1997
Reviewer, Office of Preservation Services Date

Pikunty 7/21/97
Reviewer, NR program Date

Preparer:
P.A.C. Spero & Company
September 1996

Property Address 7911 and 9110 Dyson Road, Brandywine, Prince George's County
Owner Name/Address Route 301-CPI Associates Limited Partnership/Capitol Properties Inc., 8341-A Greensboro Drive, McLean, VA 22102
Year Built 1857

Resource Sketch Map and National Register Boundary Map:



Preparer:
P.A.C. Spero & Company
September 1996

U.S. 301 South Corridor


Transportation Study

Survey # B92, PG:85A-13


Property Name GWYNN PARK

Town/County BRANDYWINE/Prince George's Co.

Quadrangle Brandywine



PG:85A-13
Gwynn Park
7911 and 9110 Dyson Road, Brandywine
Brandywine quadrangle







1. 10/20/2018
2. 10/20/2018 Prince Georges County MD
3. 10/20/2018

4. 10/20/2018 - 10/20/2018
5. 10/20/2018

6. 10/20/2018 - 10/20/2018 #2 North and
west elevations, South east view

7. 10/20/2018





2



How long have you been

Engelhardt

5th June 1900



10.11.1914. 1st day of snow & rain
M.

Coffee day

on 1st day of snow

6

1st day of snow



41



1912 (approx) 100

South and West side
of the

8



Time 10:40-11:00
197

9

10

with
bottle

10:40-11:00
197



Miss Gayle - Can.

South Cleveland 2012

view

PRINCE GEORGE'S COUNTY
HISTORIC SITE SUMMARY SHEET

Survey #: P.G. #85A-13 Building Date: 1857

Building Name: Gwynn Park

Location: 7911 Dyson Road, Brandywine, Maryland

Private/Residence/Occupied/Excellent/Inaccessible

Description

Gwynn Park is a two-and-one-half story side-gabled brick dwelling with a one-story kitchen wing attached at one gable end. The main block has a Georgian plan, and is five bays wide with entrance in the central bay of the principal west facade, through a four-panel door with three-pane transom, three-pane sidelights, and panelled jambs and soffit. Sheltering this west entrance is a one-story flat-roof entry porch; the porch frieze is embellished by large jigsaw brackets. Windows are 6/6 wood frame double hung sash, longer on the first story. There are two flush corbelled brick chimneys at each gable end. The outstanding feature of the building is the decorative molded brick cornice on the main west facade: from the top, a course of egg-and-dart molding, one course of stretchers, a course of brick mutules each with four guttae, two courses of stretchers, an enriched talon of anthemion, and a running Greek fret motif as the lower course. Extending south from the south gable end, and inset from both the east and west elevations is a one-story brick gable-roof kitchen wing. The house at Gwynn Park stands in a grove of trees on level cultivated land, with a complex of outbuildings.

Significance

Gwynn Park is an excellent example of a Georgian-plan brick plantation of the mid-nineteenth century. It is distinguished by a particularly fine decorative molded brick cornice, and is one of only two such buildings still standing in Prince George's County. Gwynn Park was built in 1857 by William H. Gwynn of Thomas, on the site of his brick dwelling which had been destroyed by fire earlier in that year. The new residence recalled an earlier Georgian style of architecture: a spacious brick structure with a central stairhall flanked by double parlors. Architectural details, however, reflected the Greek Revival style, particularly the outstanding molded brick cornice. The frame meathouse which survived the 1857 fire continued in use, and still stands east of the house. Gwynn Park remained in the Gwynn family until 1889 when it was sold to J. Eli Huntt; it remained in the possession of Huntt's heirs until 1986. Gwynn Park is a rare surviving example in Prince George's County of a mid-nineteenth century Georgian-plan brick plantation house. The only comparable dwelling is Connicks Folly built in the same year; it is the same size, and has the same plan and exterior detail as Gwynn Park, but its cornice is merely dentilled, and does not have the abundant molded details of Gwynn Park.

Acres: 293 acres

Maryland Historical Trust

State Historic Sites Inventory Form

1. Name (indicate preferred name)

historic Gwynn Park

and/or common

2. Location

street & number 7911 Dyson Road ☐ not for publicationcity, town Brandywine ^{TB} ☐ vicinity of congressional district 4

state Maryland county Prince George's

3. Classification

Category	Ownership	Status	Present Use
<input type="checkbox"/> district	<input type="checkbox"/> public	<input checked="" type="checkbox"/> occupied	<input type="checkbox"/> agriculture <input type="checkbox"/> museum
<input checked="" type="checkbox"/> building(s)	<input checked="" type="checkbox"/> private	<input type="checkbox"/> unoccupied	<input type="checkbox"/> commercial <input type="checkbox"/> park
<input type="checkbox"/> structure	<input type="checkbox"/> both	<input type="checkbox"/> work in progress	<input type="checkbox"/> educational <input checked="" type="checkbox"/> private residence
<input type="checkbox"/> site	Public Acquisition	Accessible	<input type="checkbox"/> entertainment <input type="checkbox"/> religious
<input type="checkbox"/> object	<input type="checkbox"/> in process	<input type="checkbox"/> yes: restricted	<input type="checkbox"/> government <input type="checkbox"/> scientific
	<input type="checkbox"/> being considered	<input type="checkbox"/> yes: unrestricted	<input type="checkbox"/> industrial <input type="checkbox"/> transportation
	<input checked="" type="checkbox"/> not applicable	<input checked="" type="checkbox"/> no	<input type="checkbox"/> military <input type="checkbox"/> other:

4. Owner of Property (give names and mailing addresses of all owners)

name Gwynn Park Limited Partnership

street & number P.O. Box 68 telephone no.:

city, town Brandywine state and zip code Maryland 20613

5. Location of Legal Description

courthouse, registry of deeds, etc. Prince George's County Courthouse liber 6515

street & number Main Street folio 565

city, town Upper Marlboro state Maryland 20772

6. Representation in Existing Historical Surveys

title HABS 1936 (Library of Congress)/P.G. Historic Sites and Districts Plan

date 1981 ☐ federal ☐ state ☒ county ☐ local

depository for survey records P.G. Co. Historic Preservation Commission c/o M-NCPPC

city, town Upper Marlboro state Maryland 20772

7. Description

Survey No. P.G.#85-13

Condition		Check one	Check one
<input checked="" type="checkbox"/> excellent	<input type="checkbox"/> deteriorated	<input type="checkbox"/> unaltered	<input checked="" type="checkbox"/> original site
<input type="checkbox"/> good	<input type="checkbox"/> ruins	<input checked="" type="checkbox"/> altered	<input type="checkbox"/> moved date of move _____
<input type="checkbox"/> fair	<input type="checkbox"/> unexposed		

Prepare both a summary paragraph and a general description of the resource and its various elements as it exists today.

Gwynn Park is a two-and-one-half story side-gabled brick dwelling with a one-story kitchen wing attached at one gable end. It stands on level ground in a grove of trees surrounded by cultivated fields; it is distinguished by a particularly fine decorative molded brick cornice.

The main block has a Georgian plan, and is five bays wide with entrance in the central bay of the principal west facade. Entrance is through a four-panel door with three-pane transom and three-pane sidelights over molded panels. The door has a plain board surround with crown molding under the transom, and its jambs and soffit are deeply panelled. Sheltering this west entrance is a one-story flat-roof entry porch supported by pairs of square panelled posts which rest on brick bases. The wide board frieze of the porch is embellished by large jigsaw brackets with decorative pendants. The flat roof of the porch is bounded by a plain rail balustrade which forms a balcony at the second story. The porch has a concrete floor on a brick foundation, and is approached by a flight of concrete steps.

The brick walls of Gwynn Park are laid in 5:1 American bond. Windows are 6/6 wood frame double hung sash, longer on the first story; they have narrow molded surrounds, and wood sills, painted white. Windows on the main west facade have wide wood lintels with crown molding, painted white, and louvered wood shutters painted dark green. Windows in the east (rear) elevation have the same narrow surrounds and sills, but are surmounted by flat arches in the brick, and have no shutters. The second story window in the central bay of the east elevation is downset to light the stairhall. There is a single 6/6 window at loft level in each of the east and west gable ends.

The gable roof is covered with gray asbestos shingles. There are two flush corbelled brick chimneys at each gable end, each breaking through the plain white raking board. Two small gable dormers pierce the east plane of the roof; each encloses a 6/6 window, has returned cornices, and is sided with wide white synthetic siding. The brick foundation encloses a cellar under the south part of the main block; entrance is by a bulkhead opening in the first (southmost) bay of the east facade. The half cellar is lighted by three three-pane awning-type windows. The corresponding cellar windows in the two north bays of the west facade are false: bricks painted black and white to simulate panes and muntins, between an actual white lintel and sill.

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM

Survey No. P.G.#85A-13

Description (continued)

Section 7 Page 2

The outstanding feature of the building is the decorative molded brick cornice on the main west facade: from the top, a course of egg-and-dart molding, one course of stretchers, a course of brick mutules each with four guttae, two courses of stretchers, an enriched talon of anthemion, and a running Greek fret motif as the lower course. The cornice on the east (rear) elevation is much simpler than that of the west facade; it consists of three courses of plain corbelled brick.

Extending south from the south gable end, and inset from both the east and west elevations is a one-story brick gable-roof kitchen wing. It is three bays by one, with entrance in the first bay of the west facade, through a plain modern door approached by a flight of concrete steps. At the south gable end of the wing is an exterior corbelled brick chimney with weatherings; the roof covering is the same as the main block. The cornice is defined by two courses of plain corbelled brick, and the gable end by plain raking boards painted white. Windows in the wing are 6/6 double hung sash topped by flat brick arches; they have narrow molded surrounds, wood sills painted white, and louvered wood shutters painted dark green. The east (rear) elevation of the wing is sheltered by a shed-roof porch now enclosed with white aluminum siding to form a sun porch. Its roof is covered with standing seam metal.

The interior of Gwynn Park was not observed during this survey. It has a Georgian plan: central stairhall flanked on each side by two parlors, each one warmed by a fireplace in its end wall. An archival photograph from circa 1920 shows the stairhall: the open-string stair rises along the south wall of the stairhall and turns 90 degrees at a landing lighted by the downset window, then turns 90 degrees again and rises to the second story; it has a heavy turned newel with octagonal base, turned balusters and scroll-bracketed stair-ends; the spandrel under the first three steps is panelled; the remainder of the area under the stair is open, leading to the four-panelled rear door centered in the east facade.

The house at Gwynn Park stands in a grove of trees on level cultivated land, with a complex of outbuildings. Directly behind (to the east of) the house is a meat house, a small barn and corn crib stand to the south, a modern garage immediately to the north, and a large tobacco barn further to the north in the middle of the field.

The frame meat house is square (roughly 12 by 12 feet) with gable roof; its hand-split wide board siding is covered with wide white composition siding. Entrance is centered in the west gable end through a vertical plank door painted red; there are no windows. The gable roof is covered with corrugated red metal. This small building has hewn and pitsawn posts and diagonal braces, and hewn sill beams; studs are approximately 10 inches apart. The foundation is brick, replaced and reinforced in sections with cinder block, and the floor is of brick. The meat house predates the main house, and survived the fire of January 1857.

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM

Survey No. P.G.#85A-13

Description (continued)

Section 7 Page 3

North of the house is a modern frame garage building, accessible by a new section of drive lined on the north by forsythia. Farther north, in the north field, is a twentieth century gambrel-roof tobacco barn. It is sided with vertical board siding, and its roof is covered with standing seam metal. Entrance is in the south gambrel end. Attached on the east is a cinder-block shed-roof stripping shed.

To the south of the house, in the south field stand a small barn and corn crib. The barn has a gable roof of uneven pitch, covered with red standing seam metal. Entrance is in the north elevation through double batten doors. The barn rests on brick piers. Sill beams are hand hewn, but the vertical board siding is circular sawn. Other construction members are mixed, hand and circular sawn, and many are clearly reused from another structure. Immediately south of this barn is a corn crib clad with vertical slats; its gable roof is covered with red corrugated metal.

Cedars line the unpaved lane which leads east from Dyson Road to the house at Gwynn Park. The house itself is framed by a grove of trees including both maples and hemlocks, and a line of lilacs to be south. There are some boxwood plantings immediately west of the principal entrance. On the other side of the south field are the grounds of Gwynn Park High School, and on the west side of Dyson Road is Gwynn Park Middle School. The historic property is bounded on the east by U.S. Route 301.

8. Significance

Survey No. P.G.#85A-13

Period	Areas of Significance—Check and justify below			
<input type="checkbox"/> prehistoric	<input type="checkbox"/> archeology-prehistoric	<input type="checkbox"/> community planning	<input type="checkbox"/> landscape architecture	<input type="checkbox"/> religion
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> archeology-historic	<input type="checkbox"/> conservation	<input type="checkbox"/> law	<input type="checkbox"/> science
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> agriculture	<input type="checkbox"/> economics	<input type="checkbox"/> literature	<input type="checkbox"/> sculpture
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> architecture	<input type="checkbox"/> education	<input type="checkbox"/> military	<input type="checkbox"/> social/
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> art	<input type="checkbox"/> engineering	<input type="checkbox"/> music	<input type="checkbox"/> humanitarian
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> commerce	<input type="checkbox"/> exploration/settlement	<input type="checkbox"/> philosophy	<input type="checkbox"/> theater
<input type="checkbox"/> 1900-	<input type="checkbox"/> communications	<input type="checkbox"/> industry	<input type="checkbox"/> politics/government	<input type="checkbox"/> transportation
		<input type="checkbox"/> invention		<input checked="" type="checkbox"/> other (specify)
				Local History

Specific dates 1857

Builder/Architect

check: Applicable Criteria: ☐ A ☐ B ☐ C ☐ D
and/or

Applicable Exception: ☐ A ☐ B ☐ C ☐ D ☐ E ☐ F ☐ G

Level of Significance: ☐ national ☐ state ☐ local

Prepare both a summary paragraph of significance and a general statement of history and support.

Gwynn Park is an excellent example of a Georgian-plan brick plantation house of the mid-nineteenth century. It is distinguished by a particularly fine decorative molded brick cornice, and is one of only two such buildings still standing in Prince George's County.

The land on which Gwynn Park stands was part of the land holdings of Colonel Thomas B. Gwynn. When Colonel Gwynn died in 1853, he devised to his son, William H. Gwynn, the land which he had purchased in 1835 from the heirs of Thomas M. Mudd, and on which the younger Gwynn already resided.¹ This land lay along the east side of the road from Robeysville (Surrattsville) and TB to Charles County.

The younger Gwynn (who was known as William H. Gwynn of Thomas to distinguish him from cousins of the same name) had in 1851 married Christiana Summers, and they had built a brick house on the property.² In January of 1857, this new residence was destroyed by fire; The Planters' Advocate (published in Upper Marlboro) reported the disaster as follows: "We much regret to learn that the residence of William H. Gwynn Esq. of Thomas in Piscataway District was entirely consumed by fire on Wednesday night last. Nearly all the furniture, clothing and other contents of the house were consumed. His meat house and cornhouse caught several times, but were fortunately saved by great efforts. The fire is attributed to accident, and originated in the kitchen."³

Within a short time, the Gwynns built the present house on the site of the house that had burned. They called it Gwynn Park, and it was in this handsome house that they raised their eleven children. This fine new residence, a spacious gable-roof brick structure with a central stairhall

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM
Statement of Significance (continued)

Survey No. P.G.#85A-13
Section 8 Page 2

flanked by double parlors, recalled an earlier Georgian style of architecture. Architectural details, however, reflected the Greek Revival style of the mid-nineteenth century: the door enframingent with multi-light transom and sidelights, the heavy turned newel, the formal staircase, and most particularly the outstanding molded brick cornice. The frame meathouse which survived the 1857 fire continued in use, and still stands east of the house.

William H. Gwynn of Thomas was locally known as a generous host, and Gwynn Park was the center of much social activity in the Brandywine area. After the Civil War, however, like many planters in Prince George's County, Gwynn found himself in serious financial difficulty. In 1873, he transferred title of Gwynn Park to his wife, retaining for himself a life estate in the property.⁴ At that time the farm consisted of 510 acres. By 1889, Christiana Gwynn had died, and William Gwynn was insolvent.⁵ Trustees were appointed to dispose of William H. Gwynn's life estate in the property, and, together with the heirs of Christiana Gwynn, they sold the property to J. Eli Huntt, a prominent farmer and merchant who owned a great deal of land near TB and Brandywine, and operated a general store in TB.⁶ Huntt died in 1897, leaving all of his real estate to his widow, Laura, who in 1914 devised Gwynn Park to her daughter, Susie Huntt Dyson. Gwynn Park remained in the possession of the Huntt-Dyson heirs until 1986 when it was sold to Gwynn Park Limited Partnership.⁷

Gwynn Park is a rare surviving example in Prince George's County of a mid-nineteenth century Georgian-plan brick plantation house. The only comparable dwelling in Prince George's County is Connicks Folly (#87A-9) built in the same year (1857) for Clement and Sophia Connick, approximately eight miles southeast of Gwynn Park in the area known as Horsehead. Connicks Folly is the same size, and has the same plan and exterior detail as Gwynn Park, but the cornice of Connick's Folly is merely dentilled, and does not have the abundant molded details of Gwynn Park.

Three other ante-bellum brick plantation houses, Williams Plains (71B-3), Weston (82A-7), and Hitching Post Hill (68-1), may be compared to Gwynn Park: all three have Georgian floor plan, and Greek Revival style interior trim, but they differ widely from Gwynn Park in total detail. Gwynn Park is the only surviving building in Prince George's County with a molded brick cornice of this type. It is this seven-course cornice, highly enriched with classical Greek motifs, which makes Gwynn Park outstanding and unique.

MARYLAND HISTORICAL TRUST
STATE HISTORIC SITES INVENTORY FORM
Statement of Significance (continued)

Survey No. P.G.#85A-13

Section 8 Page 3

Notes

- 1 Prince George's County Will, PC #1:501; Prince George's County Deed AB #9:364.
- 2 Prince George's County Marriage Records; Bowie, E. G., Across the Years in Prince George's County, 1975, page 347, ff.
- 3 Planters' Advocate, 21 January 1857; Bowie, op. cit.
- 4 Prince George's County Deed, HB #8:206.
- 5 The Gwynns were members of the congregation of St. Mary's Roman Catholic Church in Piscataway, and are buried in the church yard. cf. Stones and Bones, Cemetery Records of Prince George's County, Maryland, 1984.
- 6 Prince George's County Deeds, JWB #21:354, 359, 361. Cf. MHT forms PG #85A-14, -15, -16, and -17.
- 7 Prince George's County Wills, JBP #1:394, WAM #1:599; Deeds #1891:240, 244, 247.

9. Major Bibliographical References

Survey No. P.G.#85A-13

cf. Notes Item #8

cf. Chain of Title

10. Geographical Data

Acreage of nominated property 293 acres

Tax Map 145 Parcel 166

Quadrangle name Brandywine

Quadrangle scale 1:24,000

UTM References do NOT complete UTM references

A

--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

B

--	--	--	--	--	--	--	--	--	--

Zone Easting Northing

C

--	--	--	--	--	--	--	--	--	--

D

--	--	--	--	--	--	--	--	--	--

E

--	--	--	--	--	--	--	--	--	--

F

--	--	--	--	--	--	--	--	--	--

G

--	--	--	--	--	--	--	--	--	--

H

--	--	--	--	--	--	--	--	--	--

Verbal boundary description and justification

List all states and counties for properties overlapping state or county boundaries

state	code	county	code
state	code	county	code

11. Form Prepared By

name/title Susan G. Pearl, Research/Architectural Historian

organization P.G. Historic Preservation Commission c/o M-NCPPC date June 1988

street & number Room 4010 CAB telephone 952-3521

city or town Upper Marlboro state Maryland 20772

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature to be found in the Annotated Code of Maryland, Article 41, Section 181 KA, 1974 supplement.

The survey and inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

return to: Maryland Historical Trust
Shaw House
21 State Circle
Annapolis, Maryland 21401
(301) 269-2438

CHAIN OF TITLE

Gwynn Park P.G. 85A-13

1891:244 22 July 1955 Deed	Geraldine Payne to J. Laurie Dyson and wife Hazel Dyson, all which Payne received 1891:240
1891:240 31 May 1955 Deed	Mary Dyson Hagemann and husband Milton, John F. Dyson and wife Emma, and J. Laurie Dyson and wife Hazel (all heirs of Susan G. Dyson) to Geraldine Payne, 370.785 acres Gwynn Park which Susan G. Dyson obtained by will of her mother, Laura Hunt
WAM#1:599 4 Aug 1914 Will	Testator, Laura S. Hunt; to daughter Susie Gertrude Dyson, farm called Gwynn Park (which Laura Hunt received through will of her husband, J. Eli Hunt)
JBP#1:394 16 Nov 1897 Will	Testator, J. Eli Hunt; to wife Laura, all property of every kind
JWB#21:361 25 June 1892 Deed	William B. Ehlen to J. Eli Hunt, all Gwynn Park, 510 acres, conveyed to Ehlen by JWB#21:354 and JWB#21:359
JWB#21:354 20 May 1892 Deed	Henry and Mary (Gwynn) Mudd, Thomas Gwynn, and seven other Gwynns, all heirs of William H. and Christiana Gwynn, to William B. Ehlen, all their interest in Gwynn Park, 510 acres, which Christiana Gwynn received from her husband Wm. H. Gwynn
JWB#21:359 15 June 1892 Deed	J. Eli Hunt and Laura Hunt his wife, and Aquila T. Robinson to William B. Ehlen, all their interest in Gwynn Park, 510 acres
JWB#18:561 9 June 1891 Deed	F. Snowden Hill and George C. Merrick, trustees for William H. Gwynn, insolvent, to J. Eli Hunt and Aquila T. Robinson, William H. Gwynn's life estate in Gwynn Park, over 500 acres, to hold during life of William H. Gwynn. (Christiana Gwynn is now dead and life estate in Gwynn Park is vested in her husband)
HB#8:206 9 Dec 1873 Deed	William H. Gwynn of Thomas to wife Christiana, all tracts known as Gwynn Park "upon which I now reside, composed of all tracts bequeathed me by my father, Thomas B. Gwynn"
PC:501 30 Apr 1853 Will	Testator, Thomas B. Gwynn; to son William H., and purchased from Thomas Mudd's heirs, and on which William H. Gwynn resides

P/O P166

176A.
P.247

2.00 A.
P.253

BRANDYWINE
SPECIAL
EDUCATION
'A'

9294

2.59A
P.6

1.00A.
P.60

BOARD
OF ED
3443/340
5.15 A.
P.157

BOARD OF EDUCATION
14.71 A.

R-A

6225

R-R

GWYNN PARK LTD.
PARTNERSHIP
6515/565
295.29 A.
P.166

PG 85A-13

WALTER V.
6505/431
4.54 A
P.188

J.L. DYSON
4048/527
8.94 A.
P.133

BOARD OF
EDUCATION
4048/529
10.00 A.
P.218

BOARD OF EDUCATION
3157/1, 590/363
27.57 A.
P.174

BRANDYWINE
ROAD

2.00 A.
P.178

6316

CRAIN HWY

R-A


5810/
831
2.67 A.
P.55

C-M

P/O P.166

35

P.186





PG #85A-13

Leopold Park

Prince Georges Co. MD

Lewis & Clark

April 1988

West elevation

Neg: Mrs. Kent. Thrust,

Annapolis, MD



Ps # 85A-13

Seipon Park

Prince Georges Co. MD

Susan L. Pearl

April 1988

East elevation

Nyct. Md. West. Thrust.

Annapolis, MD



PG # 85A-13

Gaynor Park

Prince Georges Co. MD

Susan H. Pearl

April 1988

Seneca elevation

Neg. Md. Hist. Trust,

Annapolis, MD



PG # 85A-13

Leopold Park
Prince Georges Co. MD

Susan H Pearl

April 1988

Detail, west cornice

Meg: Md Herd Trust
Annapolis, MD



PL # 85A-13

Stuyvesant Park

Prince Georges Co. MD


Susan L. Pease

April 1988

West entrance

7/8: Old. Nest. Thrust.

Annapolis, MD



Garyn Pitt

Prince Georges Co. MD

Lusan H. Pearl

April 1988

Mealhouse from Southwest

Wg. Md. Nat. Trust,

Annapolis, MD.

PRINCE GEORGE'S COUNTY
HISTORIC SITES SUMMARY SHEET

P.G. County Survey # 85A-13 Date 1857
Building Name Gwynn Park
Location Dyson Road, Brandywine, Md.
Open to Public yes X no

Gwynn Park is a two-story gable roofed brick house, laid in common bond, with double flush chimney at each gable end. The main (west) facade is five bays wide, with central doorway. The windows of both stories have heavy wooden lintels with ogee molded heads. The most unusual feature of the house is the cornice of molded bricks: the top course is egg-and-dart, below which is a row of stretchers supported by a row of headers set as dentils (each dentil has four "drops"); below another course of stretchers is the lowest course of leaves above a fretwork or running-wave band.

Gwynn Park was part of the land holdings of Thomas B. Gwynn which he devised to his son, William H. Gwynn of Thomas. The latter married in 1851 and built a brick house on the tract. This house burned in January 1857, and the present house is the new brick dwelling which was soon afterwards erected in its place. By then known as "Gwynn Park", this house was the center of social activity in the Brandywine area.

In 1873, William Gwynn transferred title to his wife Christiana, retaining for himself a life estate. By 1889, he was in serious financial difficulties. The estate was sold out of the family, and came into the hands of J. Eli Huntt, a prominent farmer and merchant of Brandywine. The house remains today in the possession of Huntt's descendants.

MARYLAND HISTORICAL TRUST

P.G. 85A-13

INVENTORY FORM FOR STATE HISTORIC SITES SURVEY

1 NAME

HISTORIC Gwynn Park

AND/OR COMMON

2 LOCATION

STREET & NUMBER

Dyson Road (east side)

CITY, TOWN

Brandywine

VICINITY OF

CONGRESSIONAL DISTRICT

4th

STATE

Maryland

COUNTY

P.G.

3 CLASSIFICATION

CATEGORY	OWNERSHIP	STATUS	PRESENT USE
<input type="checkbox"/> DISTRICT	<input type="checkbox"/> PUBLIC	<input checked="" type="checkbox"/> OCCUPIED	<input type="checkbox"/> AGRICULTURE <input type="checkbox"/> MUSEUM
<input checked="" type="checkbox"/> BUILDING(S)	<input checked="" type="checkbox"/> PRIVATE	<input type="checkbox"/> UNOCCUPIED	<input type="checkbox"/> COMMERCIAL <input type="checkbox"/> PARK
<input type="checkbox"/> STRUCTURE	<input type="checkbox"/> BOTH	<input type="checkbox"/> WORK IN PROGRESS	<input type="checkbox"/> EDUCATIONAL <input checked="" type="checkbox"/> PRIVATE RESIDENCE
<input type="checkbox"/> SITE	PUBLIC ACQUISITION	ACCESSIBLE	<input type="checkbox"/> ENTERTAINMENT <input type="checkbox"/> RELIGIOUS
<input type="checkbox"/> OBJECT	<input type="checkbox"/> IN PROCESS	<input type="checkbox"/> YES RESTRICTED	<input type="checkbox"/> GOVERNMENT <input type="checkbox"/> SCIENTIFIC
	<input type="checkbox"/> BEING CONSIDERED	<input type="checkbox"/> YES UNRESTRICTED	<input type="checkbox"/> INDUSTRIAL <input type="checkbox"/> TRANSPORTATION
		<input type="checkbox"/> NO	<input type="checkbox"/> MILITARY <input type="checkbox"/> OTHER

4 OWNER OF PROPERTY

NAME J. Laurie Dyson

Telephone #:

STREET & NUMBER

Dyson Road

CITY, TOWN

Brandywine

VICINITY OF

STATE, zip code
Maryland 20613

5 LOCATION OF LEGAL DESCRIPTION

COURTHOUSE,
REGISTRY OF DEEDS, ETC.

P.G. County Courthouse

Liber #: 1891

Folio #: 244

STREET & NUMBER

Main Street

CITY, TOWN

Upper Marlboro

Md.

STATE

6 REPRESENTATION IN EXISTING SURVEYS

TITLE HABS - Library of Congress

Prince George's County Inventory of Historic Sites

DATE

1974

☐ FEDERAL ☐ STATE ☒ COUNTY ☐ LOCAL

DEPOSITORY FOR
SURVEY RECORDS

Calvert Mansion, 4811 Riverdale Road

CITY, TOWN

Riverdale,

STATE

7 DESCRIPTION

PG:85A-13

CONDITION

—EXCELLENT
X —GOOD
—FAIR

—DETERIORATED
—RUINS
—UNEXPOSED

CHECK ONE

—UNALTERED
X —ALTERED

CHECK ONE

—ORIGINAL SITE
—MOVED DATE _____

DESCRIBE THE PRESENT AND ORIGINAL (IF KNOWN) PHYSICAL APPEARANCE

Gwynn Park is a two story gable roofed brick house, laid up in common bond, with double flush chimney at each gable end. The main (west) facade is five bays wide with central doorway. The windows of both stories have heavy wooden lintels with ogee molding. The most unusual feature of the house is the cornice of molded bricks: the top course is egg-and-dart, below which is a row of stretchers supported by a row of headers set as dentils (each dentil has four "drops"); below another course of stretchers is the lowest course of leaves above a fretwork or running-wave band.

CONTINUE ON SEPARATE SHEET IF NECESSARY

8 SIGNIFICANCE

PERIOD		AREAS OF SIGNIFICANCE -- CHECK AND JUSTIFY BELOW			
<input type="checkbox"/> PREHISTORIC	<input type="checkbox"/> ARCHEOLOGY-PREHISTORIC	<input type="checkbox"/> COMMUNITY PLANNING	<input type="checkbox"/> LANDSCAPE ARCHITECTURE	<input type="checkbox"/> RELIGION	
<input type="checkbox"/> 1400-1499	<input type="checkbox"/> ARCHEOLOGY-HISTORIC	<input type="checkbox"/> CONSERVATION	<input type="checkbox"/> LAW	<input type="checkbox"/> SCIENCE	
<input type="checkbox"/> 1500-1599	<input type="checkbox"/> AGRICULTURE	<input type="checkbox"/> ECONOMICS	<input type="checkbox"/> LITERATURE	<input type="checkbox"/> SCULPTURE	
<input type="checkbox"/> 1600-1699	<input checked="" type="checkbox"/> ARCHITECTURE	<input type="checkbox"/> EDUCATION	<input type="checkbox"/> MILITARY	<input type="checkbox"/> SOCIAL/HUMANITARIAN	
<input type="checkbox"/> 1700-1799	<input type="checkbox"/> ART	<input type="checkbox"/> ENGINEERING	<input type="checkbox"/> MUSIC	<input type="checkbox"/> THEATER	
<input checked="" type="checkbox"/> 1800-1899	<input type="checkbox"/> COMMERCE	<input type="checkbox"/> EXPLORATION/SETTLEMENT	<input type="checkbox"/> PHILOSOPHY	<input type="checkbox"/> TRANSPORTATION	
<input type="checkbox"/> 1900-	<input type="checkbox"/> COMMUNICATIONS	<input type="checkbox"/> INDUSTRY	<input type="checkbox"/> POLITICS/GOVERNMENT	<input type="checkbox"/> OTHER (SPECIFY)	
		<input type="checkbox"/> INVENTION			

x local history

SPECIFIC DATES 1857

BUILDER/ARCHITECT

STATEMENT OF SIGNIFICANCE

Gwynn Park was part of the land holdings of Thomas B. Gwynn which he devised to his son, William H. Gwynn of Thomas.¹ William married in 1851, and built a brick house on the tract. This house burned in January of 1857², and the present house is the new brick dwelling which was soon afterwards erected in its place. By then known as "Gwynn's Park", this brick house was the center of much social nativity in the Brandywine area.

In 1873 William Gwynn of Thomas transferred title of Gwynn Park to his wife, Christiana, retaining for himself a life estate.³ By 1889, Gwynn was in serious financial difficulty. The estate was sold out of the family, and after a series of transfers, including the rights and interests in the property of William and Christiana Gwynn's heirs, came into the hands of J. Eli Hunt⁴, a prominent farmer and merchant of TB near Brandywine. The house remains today in the possession of Hunt's descendants.

1. PG. County Will: PC:501

2. Planters' Advocate, 21 January 1857

3. P.G. County Deed: HB#8:206

4. " JWB#21:361

9 MAJOR BIBLIOGRAPHICAL REFERENCES

PG:85A-13

P.G. County Deeds: HB#8:206; JWB#18:561; JWB#21:359,354,361;
1891:240, 244.

Wills: PC:501; JBP#1:394; WAM:599

Planters' Advocate, 21 January 1857

CONTINUE ON SEPARATE SHEET IF NECESSARY

10 GEOGRAPHICAL DATA

ACREAGE OF NOMINATED PROPERTY _____

VERBAL BOUNDARY DESCRIPTION

LIST ALL STATES AND COUNTIES FOR PROPERTIES OVERLAPPING STATE OR COUNTY BOUNDARIES

STATE

COUNTY

STATE

COUNTY

11 FORM PREPARED BY

NAME / TITLE

Susan G. Pearl

Project Co-ordinator

ORGANIZATION

P.G. Historical & Cultural Trust

DATE

March 1980

STREET & NUMBER

Calvert Mansion, 4811 Riverdale Road

TELEPHONE

779-2011

CITY OR TOWN

Riverdale, Maryland 20840

STATE

The Maryland Historic Sites Inventory was officially created by an Act of the Maryland Legislature, to be found in the ... Annotated Code of Maryland, Article 41, Section 181 KA, 1974 Supplement.


The Survey and Inventory are being prepared for information and record purposes only and do not constitute any infringement of individual property rights.

RETURN TO: Maryland Historical Trust
The Shaw House, 21 State Circle
Annapolis, Maryland 21401
(301) 267-1438

CHAIN OF TITLE

Gwynn Park P.G. 85A-13

1891:244 22 July 1955 Deed	Geraldine Payne to J. Laurie Dyson and wife Hazel Dyson, all which Payne received 1891:240
1891:240 31 May 1955 Deed	Mary Dyson Hagemann and husband Milton, John F. Dyson and wife Emma, and J. Laurie Dyson and wife Hazel (all heirs of Susan G. Dyson) to Geraldine Payne, 370.785 acres Gwynn Park which Susan G. Dyson obtained by will of her mother, Laura Huntt
WAM#1:599 4 Aug 1914 Will	Testator, Laura S. Huntt; to daughter Susie Gertrude Dyson, farm called Gwynn Park (which Laura Huntt received through will of her husband, J. Eli Huntt)
JBP#1:394 16 Nov 1897 Will	Testator, J. Eli Huntt; to wife Laura, all property of every kind
JWB#21:361 25 June 1892 Deed	William B. Ehlen to J. Eli Huntt, all Gwynn Park, 510 acres, conveyed to Ehlen by JWB#21:354 and JWB#21:359
JWB#21:354 20 May 1892 Deed	Henry and Mary (Gwynn) Mudd, Thomas Gwynn, and seven other Gwynns, all heirs of William H. and Christiana Gwynn, to William B. Ehlen, all their interest in Gwynn Park, 510 acres, which Christiana Gwynn received from her husband Wm. H. Gwynn
JWB#21:359 15 June 1892 Deed	J. Eli Huntt and Laura Huntt his wife, and Aquila T. Robinson to William B. Ehlen, all their interest in Gwynn Park, 510 acres
JWB#18:561 9 June 1891 Deed	F. Snowden Hill and George C. Merrick, trustees for William H. Gwynn, insolvent, to J. Eli Huntt and Aquila T. Robinson, William H. Gwynn's life estate in Gwynn Park, over 500 acres, to hold during life of William H. Gwynn. (Christiana Gwynn is now dead and life estate in Gwynn Park is vested in her husband)
HB#8:206 9 Dec 1873 Deed	William H. Gwynn of Thomas to wife Christiana, all tracts known as Gwynn Park "upon which I now reside, composed of all tracts bequeathed me by my father, Thomas B. Gwynn"
PC:501 30 Apr 1853 Will	Testator, Thomas B. Gwynn; to son William H., and purchased from Thomas Mudd's heirs, and on which William H. Gwynn resides



170435404
P.A.#85A-13

MARYLAND HISTORICAL TRUST WORKSHEET

NOMINATION FORM for the NATIONAL REGISTER OF HISTORIC PLACES, NATIONAL PARKS SERVICE

1. NAME				
COMMON:				
AND/OR HISTORIC: Gwynn Park				
2. LOCATION				
STREET AND NUMBER: Dyson Road				
CITY OR TOWN: Brandywine				
STATE: Maryland			COUNTY: Prince George's	
3. CLASSIFICATION				
CATEGORY (Check One)		OWNERSHIP		STATUS
<input type="checkbox"/> District <input type="checkbox"/> Site <input type="checkbox"/> Object		<input checked="" type="checkbox"/> Building <input type="checkbox"/> Structure <input type="checkbox"/> Public <input checked="" type="checkbox"/> Private <input type="checkbox"/> Both		<input checked="" type="checkbox"/> Occupied <input type="checkbox"/> Unoccupied <input type="checkbox"/> Preservation work in progress
PRESENT USE (Check One or More as Appropriate)		Public Acquisition: <input type="checkbox"/> In Process <input type="checkbox"/> Being Considered		ACCESSIBLE TO THE PUBLIC Yes: <input type="checkbox"/> Restricted <input type="checkbox"/> Unrestricted <input checked="" type="checkbox"/> No
<input type="checkbox"/> Agricultural <input type="checkbox"/> Commercial <input type="checkbox"/> Educational <input type="checkbox"/> Entertainment <input type="checkbox"/> Government <input type="checkbox"/> Industrial <input type="checkbox"/> Military <input type="checkbox"/> Museum <input type="checkbox"/> Park <input checked="" type="checkbox"/> Private Residence <input type="checkbox"/> Religious <input type="checkbox"/> Scientific <input type="checkbox"/> Transportation <input type="checkbox"/> Other (Specify) _____				
4. OWNER OF PROPERTY				
OWNER'S NAME: John F. Dyson				
STREET AND NUMBER:				
CITY OR TOWN: Brandywine			STATE: Maryland	
5. LOCATION OF LEGAL DESCRIPTION				
COURTHOUSE, REGISTRY OF DEEDS, ETC.: Prince George's County Courthouse				
STREET AND NUMBER:				
CITY OR TOWN: Upper Marlboro			STATE: Maryland	
Title Reference of Current Deed (Book & Pg. #):				
6. REPRESENTATION IN EXISTING SURVEYS				
TITLE OF SURVEY: Historic American Buildings Survey				
DATE OF SURVEY: 1936 <input checked="" type="checkbox"/> Federal <input type="checkbox"/> State <input type="checkbox"/> County <input type="checkbox"/> Local				
DEPOSITORY FOR SURVEY RECORDS: Library of Congress				
STREET AND NUMBER: 10 First St. SE				
CITY OR TOWN: Washington, DC			STATE:	

SEE INSTRUCTIONS

7. DESCRIPTION

CONDITION	(Check One)					
	<input type="checkbox"/> Excellent	<input checked="" type="checkbox"/> Good	<input type="checkbox"/> Fair	<input type="checkbox"/> Deteriorated	<input type="checkbox"/> Ruins	<input type="checkbox"/> Unexposed
	(Check One)			(Check One)		
	<input checked="" type="checkbox"/> Altered	<input type="checkbox"/> Unaltered	<input type="checkbox"/> Moved	<input checked="" type="checkbox"/> Original Site		

DESCRIBE THE PRESENT AND ORIGINAL (if known) PHYSICAL APPEARANCE

The house is a two story, brick structure, laid up in common bond, with double flush gable chimneys on either end, and set on a high foundation. The main (west) facade is five bays with a central doorway and 6/6 double hung sash windows. The windows have heavy wooden lintels with ogee moulded heads. The doorway has a three light transom and three light side-lights. The door has heavy moulded panels. The porch covers the central bay with bracketed cornice and double posts. The cornice of the house is of moulded brick; the top course is egg and dart moulding, below which is a row of stretchers supported by a row of headers set as dentils, below which is another row of headers. The lowest course is foliations above a fretwork band.

On the south end is a one story A-roofed wing with an exterior chimney on the south end. It is three bays with jack arches over the windows; the sash are 6/6 double hung.

In plan, the house has a central hall with a large room on the north end and two rooms on the south end. The staircase rises along the south hall wall. The interior partition walls are all brick. The interior was partially remodelled in the 1930's.

SEE INSTRUCTIONS

8. SIGNIFICANCE**PERIOD (Check One or More as Appropriate)**

- | | | | |
|--|---------------------------------------|--|---------------------------------------|
| <input type="checkbox"/> Pre-Columbian | <input type="checkbox"/> 16th Century | <input type="checkbox"/> 18th Century | <input type="checkbox"/> 20th Century |
| <input type="checkbox"/> 15th Century | <input type="checkbox"/> 17th Century | <input checked="" type="checkbox"/> 19th Century | |

SPECIFIC DATE(S) (If Applicable and Known)**1847****AREAS OF SIGNIFICANCE (Check One or More as Appropriate)**

- | | | | |
|---|---|--|--|
| <input type="checkbox"/> Aboriginal | <input type="checkbox"/> Education | <input type="checkbox"/> Political | <input type="checkbox"/> Urban Planning |
| <input type="checkbox"/> Prehistoric | <input type="checkbox"/> Engineering | <input type="checkbox"/> Religion/Philosophy | <input type="checkbox"/> Other (Specify) |
| <input type="checkbox"/> Historic | <input type="checkbox"/> Industry | <input type="checkbox"/> Science | _____ |
| <input type="checkbox"/> Agriculture | <input type="checkbox"/> Invention | <input type="checkbox"/> Sculpture | _____ |
| <input type="checkbox"/> Architecture | <input type="checkbox"/> Landscape Architecture | <input type="checkbox"/> Social/Humanitarian | _____ |
| <input type="checkbox"/> Art | <input type="checkbox"/> Literature | <input type="checkbox"/> Theater | _____ |
| <input type="checkbox"/> Commerce | <input type="checkbox"/> Military | <input type="checkbox"/> Transportation | _____ |
| <input type="checkbox"/> Communications | <input type="checkbox"/> Music | | _____ |
| <input type="checkbox"/> Conservation | | | _____ |

STATEMENT OF SIGNIFICANCE

SEE INSTRUCTIONS

9. MAJOR BIBLIOGRAPHICAL REFERENCES

10. GEOGRAPHICAL DATA

LATITUDE AND LONGITUDE COORDINATES DEFINING A RECTANGLE LOCATING THE PROPERTY				O R	LATITUDE AND LONGITUDE COORDINATES DEFINING THE CENTER POINT OF A PROPERTY OF LESS THAN TEN ACRES				
CORNER	LATITUDE				LONGITUDE				
	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds	Degrees	Minutes	Seconds
NW	°	'	"	°	'	"	°	'	"
NE	°	'	"	°	'	"	°	'	"
SE	°	'	"	°	'	"	°	'	"
SW	°	'	"	°	'	"	°	'	"

APPROXIMATE ACREAGE OF NOMINATED PROPERTY:

Acreage Justification:

SEE INSTRUCTIONS

11. FORM PREPARED BY

NAME AND TITLE:

Christopher Owens, Park Historian

ORGANIZATION

M-NCPPC

DATE

13 Aug 74

STREET AND NUMBER:

8787 Georgia Avenue

CITY OR TOWN:

Silver Spring

STATE

Maryland


12.

State Liaison Officer Review: (Office Use Only)

Significance of this property is:

National ☐ State ☐ Local ☐

Signature

1. STATE Md. COUNTY PG. TOWN STREET NO. Dysons Rd. near TB VICINITY #77 ORIGINAL OWNER ORIGINAL USE priv dwell PRESENT OWNER W.D.Cave PRESENT USE same WALL CONSTRUCTION brick NO. OF STORIES 2 1/2		HISTORIC AMERICAN BUILDINGS SURVEY INVENTORY 2. NAME 'GWYNN PARK (DFR) DATE OR PERIOD 1790-1820 STYLE Federal ARCHITECT BUILDER 3. FOR LIBRARY OF CONGRESS USE	
4. NOTABLE FEATURES, HISTORICAL SIGNIFICANCE AND DESCRIPTION <p> 4 in-set chimneys. asphalt schingle porch, woodwork, and front door are not original small 1 1/2 story extention on south small modern cottage to n.e. nice grounds cedar-lined entrance good cond. no danger </p>		OPEN TO PUBLIC	
5. PHYSICAL CONDITION OF STRUCTURE Endangered		Interior Exterior	
6. LOCATION MAP (Plan Optional) 		7. PHOTOGRAPH Color # 851	
8. PUBLISHED SOURCES (Author, Title, Pages) INTERVIEWS, RECORDS, PHOTOS, ETC. Forman, Early Manor... 1934, p 83, 95 (detail)		9. NAME, ADDRESS AND TITLE OF RECORDER DATE OF RECORD	

SUPPLEMENTAL INFORMATION AND NOTES CAPS MAY BE ADDED ON SHEET OF SAME SIZE



NAME Gwynn Park


PG 53A-13

LOCATION DYSON RD., T.B., MD.

FACADE W

PHOTO TAKEN 8/13/74

M. DWYER



NAME QWYN PARK

PG 1854-13

LOCATION DYSON RD., T.B., MD.

FACADE SE

PHOTO TAKEN 8/13/74

M. QUAYER